


REPUBLIC OF NAMIBIA  
OSHANA REGIONAL COUNCIL



Tel: +264 65 2288200  
Fax: +264 65 221292  
E-mail: PMU@oshanarc.gov.na  
Enquiries: Alma N. Kamulilo

Private Bag 5543  
Oshakati, Namibia

13 June 2025

**TO: ALL POTENTIAL BIDDERS**

**SUBJECT: CLARIFICATION ON THE BIDDING DOCUMENT FOR ROAD MAINTENANCE WORKS IN EHEKE SETTLEMENT (REF. NO. W/RFQ/ONARC-36/2025/2026).**

1. In terms of the Public Procurement Act No. 15 of 2015, Regulation 34 (4) & (5) the following clarifications on the below-mentioned bidding documents are hereby issued.

➤ **Omission of word Rate only on page 2 and section 4-7 under Price Activity Schedule.**

It has been observed that under item 2.1.3 on page 3 the word "Rate Only" and section 4-7 (page 7-10) was omitted and it has been added on the bill of quantity.


2. Furthermore, the deadline for submission of the above-mentioned bid document is extended to **26 June 2025.**

3. Kindly take this correction into account when preparing your submissions. We apologize for any confusion this may have caused and appreciate your attention to this matter.

Should you have any further questions or require clarification, please do not hesitate to contact us.

I trust you will find the above lucid.

Yours Faithfully

  
ALMA N. KAMULILO  
PMU HEAD



## ADDENDUM I

### SECTION IV: PRICED ACTIVITY SCHEDULE

In terms of the Public Procurement Regulations: Public Procurement Act, 2015 Regulation 34 (4), that, Priced Activity Schedule, as from page 2 (section 1-7), is repealed by Addendum I as amended.

*[Complete the unit and total prices for each item listed below. Authorise the prices quoted in the signature block below.]*

*The quantities shown below are approximate and subject to re-measurement for payment purposes*

**OSHANA REGIONAL COUNCIL**

**ROAD MAINTENANCE WORKS IN EHEKE SETTLEMENT**

**REF. NO: W/RFQ/ONARC-36/2025/2026**

#### SECTION 1: PRELIMINARY AND GENERAL

ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE	AMOUNT N\$
	<b>SABS 1200A</b>	<b>SECTION 1: PRELIMINARY AND GENERAL</b>				
1.1	8.3	<u>SCHEDULED FIXED-CHARGE AND VALUE RELATED ITEMS</u>				
1.1.1	8.3.2	Establishment of Facilities on the Site	Sum	1.0		
1.1.2	8.3.3	Other Fixed-charge obligations	Sum	1.0		
1.1.3	8.3.4	Removal of Site Establishment	Sum	1.0		
1.2	8.4	<u>SCHEDULED TIME-RELATED ITEMS</u>				
1.2.1	8.4.1	Contractual Requirements	Sum	1.0		
1.2.2	8.4.2	Operation and Maintenance of Facilities on Site				
		(a) Offices and storage sheds	Sum	1.0		
		(e) Ablution and latrine facilities	Sum	1.0		
1.3	8.5	<u>PROVISIONAL SUMS</u>				
1.2.3		Location, exposure, protection and/or move existing services	Prov. Sum		\	\
1.2.4		Additional tests ordered by the Engineer (including overheads, charges and profits)	Prov. Sum			10,000.00
SUB-TOTAL FOR SECTION 1: PRELIMINARY AND GENERAL (CARRIED FORWARD TO SUMMARY)						

**OSHANA REGIONAL COUNCIL**  
**ROAD MAINTENANCE WORKS IN EHEKE**  
**SETTLEMENT**  
**REF. NO: W/RFQ/ONARC-36/2025/2026**

**SECTION 2: BLADING & RESHAPING**

ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE	AMOUNT N\$
2		<b>SECTION 2: BLADING &amp; RESHAPING</b>				
2.1		<u>BLADING</u>  <i>Maximum of Four (4) blades pass to be done per road width. Rate is for one blade per kilometer</i>				
2.1.1		Light blading	Bl-km	15.0		
2.1.2		Heavy blading	Bl-km			Rate Only
2.1.3		Water the road width with a water bowser truck	m <sup>2</sup>			Rate Only
2.2		<u>RESHAPING</u>  <i>Rip to minimum depth of 100mm, mix and process with water, reshape gravel road to the specified cross section and compact to 95% modified AASHTO maximum density</i>				
2.2.1		Reshaping gravel road	m <sup>2</sup>	2 010.0		
SUB-TOTAL FOR SECTION 2: BLADING & RESHAPING (CARRIED FORWARD TO SUMMARY)						

**OSHANA REGIONAL COUNCIL**  
**ROAD MAINTENANCE WORKS IN EHEKE**  
**SETTLEMENT**  
**REF. NO: W/RFQ/ONARC-36/2025/2026**

**SECTION 3: EARTHWORKS (ROADS, SUBGRADE)**

ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE	AMOUNT N\$
3	SABS 1200 DM	<b>SECTION 3: EARTHWORKS (ROADS, SUBGRADE)</b>				
3.1		<u>TREATMENT OF ROAD-BED</u>				
	8.3.3(a) PSDM-4.1	Road-bed preparation and compaction of material of:				
3.1.1		Rip, process and compact In-situ material 150mm to 93% Mod AASHTO density	m <sup>3</sup>	1 650.0		
3.2		<u>EARTHWORKS</u>				
		Borrow to fill from borrow pit:				
3.2.1		Compact to 93% mod AASHTO density	m <sup>3</sup>	1 020.0		
3.3		<u>SELECTED LAYER</u>				
3.3.1		Compact 150 mm of G7 selected layer to 95% mod AASHTO maximum density in road layerworks	m <sup>3</sup>	962.0		
SUB-TOTAL FOR SECTION 3: EARTHWORKS (ROADS, SUBGRADE)(CARRIED FORWARD TO SUMMARY)						

**OSHANA REGIONAL COUNCIL**  
**ROAD MAINTENANCE WORKS IN EHEKE**  
**SETTLEMENT**  
**REF NO: W/RFQ/ONARC-36/2025/2026**

**SECTION 4: REGRAVELLING (SUBBASE & GRAVEL WEARING COURSE)**

ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE	AMOUNT N\$
4	SABS 1200 ME	<b>SECTION 4: REGRAVELLING (SUBBASE &amp; GRAVEL WEARING COURSE)</b>				
	8.3.1 PSME-1.1.1	<i>Construct subbase / Gravel Wearing Course with imported material from borrow pits in all materials for all roads, including unlimited free-haul:</i>				
4.1		150mm G6 Gravel Wearing Course compacted to 95% Modified AASHTO maximum density, as per TRH 20 material specification	m <sup>3</sup>	1 870.0		
SUB-TOTAL FOR SECTION 4: REGRAVELLING (CARRIED FORWARD TO SUMMARY)						

OSHANA REGIONAL COUNCIL  
ROAD MAINTENANCE WORKS IN EHEKE  
SETTLEMENT  
REF. NO: W/RFQ/ONARC-36/2025/2026

SECTION 5: STORMWATER DRAINAGE

ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE	AMOUNT N\$
5		<b>SECTION 5: STORMWATER DRAINAGE</b>				
5.1		<u>EARTH SIDE DRAINS</u>				
	1200 DA	Excavation for open drains:				
5.1.1	8.3.2	Excavate and construct V-drains (Earth Side drains) in all materials, backfill and compact and dispose of surplus/unsuitable material.	m			Rate Only
5.1.2		Clearing and shaping existing open drains	m	3 820.0		
5.2		<u>CULVERTS</u>				
	8.3.2(a)	EXCAVATION Excavate in all materials for trenches backfill, compact, and dispose of surplus/unsuitable material, for pipes (box) over 500 mm diam (length) and up to 1200 mm diam (width). for total trench depth:				
5.2.1		Exceeding 0,0 m but not exceeding 1,0 m	m			Rate Only
5.2.2		Exceeding 1,0 m but not exceeding 2,0 m	m			Rate Only
5.3	SANS 1200 LE	PIPE CULVERTS (PRECAST CONCRETE)				
		Transport, bed and install portal culverts:				
5.3.1	8.2.5	a) 300 mm dia portal pipe culvert	m <sup>3</sup>			Rate Only
5.4		CAST-IN-SITU CONCRETE INLET AND OUTLET STRUCTURES				
	8.2.5	Cast in-situ concrete (including formwork, reinforcement) for inlet and outlet structures as detailed on drawing				

	<u>300mm diameter pipe culvert:</u>			
5.4.1	a) Cast-in-situ concrete 30 MPa/40 mm & Formwork for concrete structures & apron	m <sup>3</sup>		Rate Only
5.4.2	b) Mesh 395 for concrete structures & apron	m <sup>2</sup>		Rate Only
SUB-TOTAL FOR SECTION 5: STORMWATER DRAINAGE (CARRIED FORWARD TO SUMMARY)				

**OSHANA REGIONAL COUNCIL**  
**ROAD MAINTENANCE WORKS IN EHEKE**  
**SETTLEMENT**  
**REF. NO: W/RFQ/ONARC-36/2025/2026**

**SECTION 6: ANCILLARY ROADWORKS**

ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE	AMOUNT N\$
6	SANS 1200 MM	<b>SECTION 6: ANCILLARY ROADWORKS</b>				
6.1		<b>ROAD SIGNS</b>				
		Sign faces with painted or galvanized (as stated) background. Symbols, characters, legend, and borders in engineering grade retro-reflective material with signboards constructed from Aluminium sheet (2,0 mm thick) or Steel sheet as approved by the Engineer				
	8.3	Supply and install road signs complete including support and concrete works as per drawings for:				
6.1.1		(a) STOP sign 600mm	No.	15.0		
		(b) Warning signs:		6.0		
6.1.2		(i) W350 DRIFT Sign 600mm	No.			Rate Only
6.1.3		(ii) W401 (600 x 150mm) Danger plates	No.	12.0		
6.2		<b>ROAD MARKINGS</b>				
		Retro-reflective road marking paint applied at nominal rate of 0.42 litre/m <sup>2</sup> as scheduled				
		(a) White lines (broken or unbroken)				
6.2.1		(i) 100 mm wide	m			Rate Only
6.2.2		(ii) 300 mm wide	m			Rate Only
		(b) Yellow lines (broken or unbroken)				
6.2.3		(i) 150 mm wide	m			Rate Only



6.2.4		(c) White lettering and symbols	m <sup>2</sup>			Rate Only
6.2.5		Setting out and premarking the lines (excluding traffic- island markings, lettering and symbols)	m			Rate Only
SUB-TOTAL FOR SECTION 6: ANCILLARY ROADWORKS (CARRIED FORWARD TO SUMMARY)						

**OSHANA REGIONAL COUNCIL**  
**ROAD MAINTENANCE WORKS IN EHEKE**  
**SETTLEMENT**  
**REF. NO: W/RFQ/ONARC-36/2025/2026**

**SECTION 7: CLEANING AND FINISHING**

ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE	AMOUNT N\$
7	SABS	<b>SECTION 7: CLEANING AND FINISHING</b>				
	1200 D					
7.1		Cleaning and finishing of site after completion of the works and the removal of all construction rubble and debris to approved spoil sites	Sum	1.0		
SUB-TOTAL FOR SECTION 7: CLEANING AND FINISHING (CARRIED FORWARD TO SUMMARY)						

<b>SUMMARY OF SCHEDULE OF QUANTITIES</b>				
	SCHEDULE	DESCRIPTION		AMOUNT N\$
	SECTION 1:	PRELIMINARY AND GENERAL	N\$	
	SECTION 2:	BLADING & RESHAPING	N\$	
	SECTION 3:	EARTHWORKS (ROADS, SUBGRADE)	N\$	
	SECTION 4:	REGRAVELLING (SUBBASE & GRAVEL WEARING COURSE)	N\$	
	SECTION 5:	STORMWATER DRAINAGE	N\$	
	SECTION 6:	ANCILLARY ROADWORKS	N\$	
	SECTION 7:	CLEANING	N\$	
	SUB-TOTAL		N\$	
	Contingencies - Add 10% to be spent with authorization of Engineer		N\$	
	SUB-TOTAL		N\$	
	Add 15% Value Added Tax (VAT)		N\$	
	TOTAL CARRIED TO BID SUBMISSION FORM		N\$	

**Priced Activity Schedule Authorised By:**

Name:		Signature:	
Position:		Date:	
Authorised for and on behalf of:	Company		